

# ANENDA SYSTEMS INC. TEST REPORT

### **SPECIFICATION**

AAMA 508-14

### **PRODUCT EVALUATED**

AL13 V2 4mm ACM System

### **REPORT NUMBER**

102731078COQ-008

### **ISSUE DATE**


09-Mar-2018

### **PAGES**

21

### **DOCUMENT CONTROL NUMBER**

GFT-OP-10b (13-March-2017) © 2017 INTERTEK





1500 Brigantine Drive Coquitlam, BC, V3K 7C1

Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

### TEST REPORT FOR ANENDA SYSTEMS INC.

Report No.: 102731078COQ-008

Date: 09-Mar-2018

### **CONCLUSION**

The AL13 V2 4mm ACM System, submitted by Anenda Systems Inc., had met the performance requirements as noted in Section 7 of this report when tested in accordance with AAMA 508.

Note – This report is not intended as a comprehensive evaluation of the system regarding performance and application to specific buildings.

Jason Komorski TECHNICIAN

**BUILDING PRODUCTS** 

David Park
REVIEWER
BUILDING PRODUCTS

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to copy or distribute Intertek's Reports and then only in their entirety, and the Client shall not use the Reports in a misleading manner. In the event any portion of this report becomes public, including but not limited to press releases, articles, and marketing material, without prior written consent from Intertek, Intertek may enforce the reproduction of the report in its entirety by making the full report public. Client further agrees and understands that reliance upon the Reports is limited to the representations made therein. In the event any portion of this report becomes public, including but not limited to press releases, articles, and marketing material, without prior written consent from Intertek, Intertek will enforce the reproduction of the report in its entirety by making the full report public. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. Should Customer use an Intertek Report, in whole or in part, in such a manner as to involve Intertek in legal controversy or to adversely affect Intertek's reputation, it shall be Intertek's right to utilize any and all Customer information, including, but not limited to, data, records, instructions, notations, samples or documents within Intertek's custody and control which relate to the customer for the purpose of offering any necessary defense or rebuttal to such circumstances. This report by itself does not imply that the m

### **SECTION 1**

# **INDEX**

SECTION NAMES	PAGE
INDEX	3
OBJECTIVE	4
Sample selection	4
SAMPLE ASSEMBLY AND DESCRIPTION	5
TESTING AND EVALUATION METHODS.  AIR LEAKAGE  PRESSURE EQUALIZATION  WATER PENETRATION RESISTANCE – STATIC.  WATER PENETRATION RESISTANCE – DYNAMIC.  DEVIATION FROM STANDARD METHOD.	6 6 6
TEST EQUIPMENT	7
RESULTS AND OBSERVATIONS  AIR LEAKAGE  PRESSURE EQUALIZATION  WATER PENETRATION RESISTANCE – STATIC  WATER PENETRATION RESISTANCE – DYANMIC.	7 7 8
CONCLUSION	9
APPENDIX A: DRAWINGS	10
APPENDIX B: PRESSURE EQUALIZATION GRAPH	15
APPENDIX C: PHOTOGRAPHS	17
APPENDIX D: REVISION TABLE	20

TEST REPORT FOR ANENDA SYSTEMS INC.

### **SECTION 2**

### **OBJECTIVE**

Intertek Testing Services NA Ltd. (Intertek) has conducted testing for Anenda Systems Inc. on the AL13 V2 4mm ACM System. Testing was conducted in accordance with the following:

 AAMA 508-14, Voluntary Method and Specification for Pressure Equalized Rain Screen Wall Cladding Systems (AAMA 508)

This evaluation began on December 19, 2017 was completed on December 20, 2017.

### **SECTION 3**

### **SAMPLE SELECTION**

The client submitted the exterior metal composite wall panel system to the Evaluation Center on December 18, 2017. Samples were not independently selected for testing. The system/specimen was provided by Anenda Systems Inc. located at 827 Cambie Street, Vancouver, BC, Canada, V6P 2P4.

The specimen was installed and as provided by the client. Intertek has not verified the composition, manufacturing techniques, or quality assurance procedures, and accepts no responsibility for any inaccuracies therein.

### **SECTION 4**

### SAMPLE ASSEMBLY AND DESCRIPTION

The product was identified as the AL13 V2 4mm ACM System, and measured 2438 mm x 2438 mm (96" x 96"). The upper half of the wall was one panel, measuring approximately 47-1/4" by 95-1/4", and the lower half was split into two square sections, measuring approximately 47-1/4" by 47-1/4", split by a vertical joint. An aluminum perimeter track is secured with 1/4" x 1-1/2" self-tapping washer-head fasteners, approximately 76 mm (3") from the corners, and 406 mm (16") o.c. The horizontal cap snaps in to 6x track profiles, each cut approximately 83 mm (3-1/4") long. Located approximately 406 mm (16") from either end, with 406 mm (16") spacing o.c. except mid-span, where there is a track section centered approximately 76 mm (3") from either side of the mid-point. Each track section is secured with 2x 1/4" x 1-1/2" self-tapping washer-head fasteners. The vertical cap snaps in to one 1092 mm (43") long track section, secured with 4x 1/4" x 1-1/2" self-tapping washer-head fasteners, located approximately 25 mm (1") and 330 mm (13") from either end of the track. Each the perimeter track and the center horizontal and vertical tracks have composite spacer blocks slid over the edge of the perimeter track, or both edges of the center tracks. The blocks measure approximately 102 mm (4"), x 14 mm (0.55") x 20 mm (0.79") with an 18 mm (0.71") deep slot approximately 3 mm (0.12") from the interior side. The blocks along the perimeter track are spaced approximately 152 mm (6") from the corners, spaced 254 mm - 406 mm (10" - 16") o.c. The blocks along the vertical track are located approximately 102 mm (4") from either end, and mid-span.

A 96" wide by 96" high steel stud wall was constructed using 16 ga. 2x6 steel studs placed at 16" on center. The wall was then sheathed with 1/2" thick clear poly carbonate sheet. The wall panel system was then installed onto the clear polycarbonate in a manner consistent with normal construction procedures for the system. The exterior of the test unit was sealed to the wood buck with silicone.

Drawings supplied by Anenda Systems Inc. are included in Appendix A.

### **SECTION 5**

### **TESTING AND EVALUATION METHODS**

### **AIR LEAKAGE**

The Air Leakage tests (Air Infiltration) were conducted in accordance with ASTM E283. The tests were performed using a test pressure of 75 Pa (1.57 psf). As per AAMA 508, air leakage was induced in the system to provide a leakage rate of 0.6 L/s\*m<sup>2</sup>.

### PRESSURE EQUALIZATION

The Pressure Equalization test was tested in accordance with ASTM E1233 and evaluated to AAMA 508. The test was performed at a specified pressure differential of 240 Pa (5 psf) to 1200 Pa (25 psf) for a minimum of 100 cycles.

### WATER PENETRATION RESISTANCE – STATIC

The Static Water Penetration test was tested in accordance with ASTM E331 and evaluated to Section 6.1 of AAMA 508. This test was performed at the specified pressure differential of 730 Pa (15 psf) and a water spray rate of at least 204 L/m² per hour (5.0 U.S. gal/ft² per hour). The test was run for fifteen minutes, during which the pressure and water spray were continuously applied.

### WATER PENETRATION RESISTANCE – DYNAMIC

The Dynamic Water Penetration test was tested in accordance with AAMA 501.1 and evaluated to Section 6.1 of AAMA 508. The test was performed at the specified pressure differential of 720 Pa (15 psf), or 120 kph (75 mph) wind speed equivalent, generated using a Wind Generator, and a water spray rate of at least 204 L/m² per hour (5.0 U.S. gal/ft² per hour). This test consisted of fifteen minutes, during which the wind and water spray were continuously applied.

### **DEVIATION FROM STANDARD METHOD**

Structural performance was performed on a separate sample. Refer to Intertek Report No. 103193419COQ-001A.

### **SECTION 6**

### **TEST EQUIPMENT**

Equipment used during testing is listed as follows:

Test	Equipment	Intertek ID#
	Fenestration Testing Control Unit	60650
		60651
	Water Spray Assembly	60652
	Micro Mule	63170
Air Leakage, Pressure Equalization, Static Water Penetration, Structural	Rain Screen Pressure Box	INT00712
		60673
		64928
	20" Line Gauge	64926
		64923
		64920
	Wolf Wind Generator	63339
Dynamic Water Penetration	Spray Rack Assembly	ITS-1

### **SECTION 7**

### **RESULTS AND OBSERVATIONS**

### **AIR LEAKAGE**

Air leakage test data is indicated in the following table:

Test Pressure	75 Pa
Overall Area	5.94 m <sup>2</sup> (63.98 ft <sup>2</sup> )
Air Leakage	$0.60 \text{ L/s*m}^2 (0.12 \text{ cfm/ft}^2)$

### PRESSURE EQUALIZATION

During the Pressure Equalization test cycling at a pressure differential from 240 Pa (5 psf) to 1200 Pa (25 psf) for 100 cycles the systems lag times was below the required 0.08 seconds and the differential between the cavities and cyclic wind pressure did not exceed 50% of the maximum test pressure. Refer to Appendix B for a graph on 1 cycle. The tested specimen **met** the performance requirements for Pressure Equalization of AAMA 508.

### **WATER PENETRATION RESISTANCE – STATIC**

During the 15-minute test period, using a pressure differential of 730 Pa (15 psf), there was no water leakage observed through the tested sample. The sample **met** the performance requirements for Static Water Penetration of ASTM E331.

### **WATER PENETRATION RESISTANCE – DYANMIC**

During the 15-minute test period, using wind speed 120 kph (75 mph), no water leakage was observed through the tested sample. The sample **met** the performance requirements for Dynamic Water Penetration of AAMA 501.1.

### **SECTION 8**

### **CONCLUSION**

The AL13 V2 4mm ACM System, submitted by Anenda Systems Inc., had met the performance requirements as noted in Section 7 of this report when tested in accordance with AAMA 508.

Note – This report is not intended as a comprehensive evaluation of the system regarding performance and application to specific buildings.

### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018


## **SECTION 9**

**APPENDIX A: DRAWINGS** 

(4 Pages)


### TEST REPORT FOR ANENDA SYSTEMS INC.


Date: 09-Mar-2018





### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018











### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018






### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018

### **SECTION 10**

APPENDIX B: PRESSURE EQUALIZATION GRAPH (1 Page)

Date: 09-Mar-2018



### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018

### **SECTION 11**

**APPENDIX C: PHOTOGRAPHS** 

(2 Pages)

### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018



AL13 V2 4mm Cladding System

### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018



Water Penetration Resistance - Static, Test Setup

### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018

# **SECTION 12**

APPENDIX D: REVISION TABLE (1 Page)

# Benchmark and Non-standard Test Report: Report must be reproduced in its entirety

Report No.: 102731078COQ-008

### TEST REPORT FOR ANENDA SYSTEMS INC.

Date: 09-Mar-2018

Revision Table				
Date	Section	Description	Technician	Reviewer
09-Mar-2018		Original Issue Date		



# NATIONAL CERTIFIED TESTING LABORATORIES

FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200 FAX (717) 767-4100 www.nctlinc.com

### **AAMA 508-07**

### RAIN SCREEN PERFORMANCE TEST REPORT SUMMARY

### **RENDERED TO:**

AL13 Architectural Panel Systems 827 Cambie Street Vancouver BC Canada V6B 2P4

**MODEL/TYPE: 3-Section Aluminum Composite Panel** 

TITLE	SUMMARY OF RESULTS
ASTM E283 Air Infiltration 75 Pa (1.57 psf)	Confirmed rate 0.61 L/s/m <sup>2</sup> (0.12 cfm/ft <sup>2</sup> )
ASTM E331 & AAMA 501.1 Water Penetration Resistance Test Pressures	Pass at 479 Pa (10 psf)
ASTM E1288 Pressure Cycling 240 Pa (5 psf)/ 1200 (25 psf)/ 240 Pa (5 psf)	Passed 100 Cycles

Test Completion Date: 02/27/14

Reference must be made to Report Number NCTL-110-16354-1 dated 04/02/14 for complete test sample description and data. This test report is not intended as a comprehensive evaluation of the system regarding performance and application to specific buildings.

**National Certified Testing Laboratories** 

Robert Wm. DeFayette

Field Testing/ Curtain Wall Manager



# NATIONAL CERTIFIED TESTING LABORATORIES

FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200 FAX (717) 767-4100

www.nctlinc.com

### RAIN SCREEN PERFORMANCE TEST REPORT

Report Number NCTL-110-16354-1

**Report Date** 04/02/14

Report To AL13 Architectural Panel Systems

827 Cambie Street

Vancouver BC Canada V6B2P4

Starting Test Date 02/24/14 Ending Test Date 02/24/14

**Specification** AAMA 508-07, "Voluntary Test Method and Specification for Pressure Equalized Rain

Screen Wall Cladding Systems."

### **Description of Sample Tested**

Note: All dimensions are in the order (Width x Height x Thickness) unless otherwise noted.

The test specimen consisted of a (3)-section aluminum composite panels measuring 2444.75 mm x 2501.9 mm (96.25" x 98.5") overall. The panels were 2.79 mm (0.110") thick and were fastened to the vertical Z-bar with adhesive tape at the center Z-bar and an aluminum clip at the perimeter. The vertical Z-bar was fastened to a 1.02 mm (0.040") thick steel horizontal Z-bar. The verticals were fastened to the horizontals with (1) screw at each intersection. An extruded aluminum receiver was fastened with screws at the panel seams. An extruded aluminum cover was snap-fitted at the receiver. An extruded aluminum cover was fastened with screws at the exterior perimeter and employed (7) evenly spaced 6.35 mm (0.25") diameter weep holes at the bottom. (38) 3.18 mm (0.125") Holes were equally distributed 304.8 mm (12") above the horizontal seams and at the base to achieve required air leakage. A pressure tap was centered between the screen and the dens glass also a pressure tap in the chamber between the dens glass and the test wall.

### **Test Results**

<u>Paragraph</u> <u>Test</u>

5.3 Air Leakage Resistance

ASTM E283-04(12)

Barrier leakage confirmation at 75 Pa (1.57 psf).

Required Leakage =  $0.6 \text{ L/s/m}^2 (0.12 \text{ cfm/ft}^2) +/- 10\%$ 

Air Infiltration Rate =  $0.6 \text{ L/s/m}^2 (0.12 \text{ cfm/ft}^2)$ 

**Paragraph** 

5.5

Pressure Cycle Testing


Test

ASTM E1233-14 (modified per AAMA 508-07)

100 Total Cycles at maximum 3 second durations

Positive Load 240 Pa (5 psf) 1200 Pa (25 psf) Positive Load Positive Load 240 Pa (5 psf)

**NOTE:** The lag time between the cavity and the cyclic wind pressure did not exceed 0.8 seconds



**Paragraph** 

5.6

Test

Static Water Penetration Resistance

ASTM E331-00(09) with rate of 3.4 L/m<sup>2</sup>·min (5 gal/ft<sup>2</sup>·h)

1 cycle of 15 minutes at 479 Pa (10.0 psf)

**NOTE:** A stream ran down the vertical seam not penetrating the interior

**NOTE:** Small droplets formed at the vertical/ horizontal junction NOTE: Water appearing was not in excess of 5% of barrier surface

Paragraph

Test

5.7

Dynamic Water Penetration Resistance

AAMA 501.1 with rate of 3.4 L/m<sup>2</sup>·min (5 gal/ft<sup>2</sup>·h)

1 cycle of 15 minutes at 479 Pa (10.0 psf)

NOTE: Small droplets formed at the vertical/ horizontal junction NOTE: Water appearing was not in excess of 5% of barrier surface

Paragraph

Test

5.8

Static Pressure Loading

ASTM E330-14 at client specified pressures

Horizontal

No damage after positive 1200 Pa (25 psf) held for 10 seconds No damage after negative 1200 Pa (25 psf) held for 10 seconds

Measured Deflection Positive = 1.47 mm (0.058 inches)Measured Deflection Negative = 2.16 mm (0.085 inches)Measured Permanent Set Positive = 0.10 mm (0.004 inches) Measured Permanent Set Negative = 0.15 mm (0.006 inches)

<u>Vertical</u>

No damage after positive 1200 Pa (25 psf) held for 10 seconds No damage after negative 1200 Pa (25 psf) held for 10 seconds

Measured Deflection  $_{Positive}$  = 2.79 mm (0.110 inches) Measured Deflection  $_{Negative}$  = 4.39 mm (0.173 inches) Measured Permanent Set  $_{Positive}$  = <0.03 mm (<0.001 inches) Measured Permanent Set  $_{Negative}$  = 0.20 mm (0.008 inches)

### Official Observers:

Justin Bupp National Certified Testing Laboratories
Robert Wm. DeFayette National Certified Testing Laboratories
Jay Leader National Certified Testing Laboratories

This test report is not intended as a comprehensive evaluation of the system regarding performance and application to specific buildings. This test report was prepared by National Certified Testing Laboratory (NCTL), for the exclusive use of the above named client and it does not constitute certification of this product. The results are for the particular specimen tested and do not imply the quality of similar or identical products manufactured or installed from specifications identical to the tested product. The test specimen was supplied to NCTL by the above named client. NCTL is a testing lab and assumes that all information provided by the client is accurate and does not guarantee or warranty any product tested or installed.

A copy of this report will be retained by NCTL. This report does not constitute certification or approval of the product, which may only be granted by a certification program validator or recognized approval entity. All tests were conducted in full compliance with the referenced specifications and/or test methods and any deviations are noted within the results section as necessary. This report may not be reproduced, except in full, without the written consent of NCTL.

**National Certified Testing Laboratories** 

Robert Wm. DeFayette

Field Testing/ Curtain Wall Manager

JLB/ amb Attachments

Appendix A - Revision Log

Appendix B – Test Mockup Drawing (1)

Appendix C - Photographs (6)